GENERAL

G1 THESE DRAWINGS SHALL BE READ IN CONJUNCTION WITH ALL OTHER CONSULTANTS DOCUMENTS, DRAWINGS & SPECIFICATIONS AND WITH SUCH OTHER WRITTEN INSTRUCTIONS AS MAY BE ISSUED DURING THE CONTRACT AND PROJECT

G2 ALL DIMENSIONS AND CONDITIONS WHERE SHOWN ARE TO BE VERIFIED ON SITE. ENGINEERING DOCUMENTS ARE DIAGRAMMATIC AND MUST NOT BE SCALED. DISCREPANCIES IN ANY OF THE CONTRACT DOCUMENTS SHALL BE REFERRED TO THE DESIGN ENGINEER PRIOR TO PROCEEDING WITH THE WORK.

G3 MATERIALS & WORKMANSHIP ARE TO BE IN ACCORDANCE WITH THE RELEVANT CURRENT AUSTRALIAN STANDARDS & THE BUILDING CODE OF AUSTRALIA & ALL RELEVANT AUTHORITIES HAVING ANY JURISDICTION OVER ANY PART OF THE WORKS.

G4 THESE NOTES ARE A SUPPLEMENT TO AND DO NOT REPLACE THE SPECIFICATIONS TO WHICH THE CONTRACTOR MUST CONFORM. SUBSTITUTION SHALL NOT BE PERMITTED WITHOUT THE APPROVAL OF THE ENGINEER.

G5 IT IS THE BUILDERS RESPONSIBILITY TO ENSURE THAT THE STRUCTURE & WORKS ARE MAINTAINED IN A STABLE CONDITION. NO PART SHALL BE OVER STRESSED DURING CONSTRUCTION.

G6 DESIGN LIVE LOADS:

ROOF:		0.25 KPa
FLOOR:		
-	DWELLING	1.5 KPa
-	GARAGE	2.5 KPa
BALCONY:		2.0 KPa

G7 INSPECTIONS: NO RESPONSIBILITY SHALL BE TAKEN UNLESS THE WORK IS INSPECTED AND APPROVED DURING CONSTRUCTION; ALL INSPECTION REQUIRED SHALL BE CONFIRMED 24 HOURS IN ADVANCE OF TIME REQUIRED

G8 HOME & INDUSTRIAL DOCUMENTS ARE NOT TO BE REPRODUCED IN FULL OR PART WITHOUT THE APPROVAL OF THIS OFFICE

G9 THE ARCHITECT IS TO REVIEW HOME & INDUSTRIAL CONSULTING ENGINEERS DOCUMENTS TO ENSURE CONSISTENCY WITH EXISTING CONDITIONS AND ANY RELEVANT CONSULTANT DOCUMENTS PRIOR TO ISSUE.

G10 NOT ALL SERVICES & DETAILS ARE IDENTIFIED ON THE DRAWINGS AND THE LOCATIONS ARE INDICATIVE ONLY. THE CONTRACTOR SHALL VERIFY THAT ALL REQUIREMENTS & EXISTING CONDITIONS AFFECTING THE WORKS ARE INCORPORATED INTO TENDER PRIOR TO COMMENCING THE WORK.

G11 WHERE WALLS ARE NOMINATED TO BE DEMOLISHED, CONTRACTOR TO VERIFY WITH DESIGN ENGINEER IF EXISTING CONDITION IS LOAD BEARING PRIOR TO COMMENCEMENT OF WORK.

CONCRETE

C1 CONCRETE CHARACTERISTIC COMPRESSION STRENGTH (f'c) TO BE 20 MPa MINIMUM AT 28 DAYS OR AS NOTED ON DRAWINGS. MAXIMUM SLUMP 100mm & 20MM NOMINAL AGGREGATE.

C2 CONCRETE FINISHES SHALL BE IN ACCORDANCE WITH THE SPECIFICATIONS OR ARCHITECTURAL DETAILS.

C3 CLEAR CONCRETE COVER TO NON PRE STRESSED REINFORCEMENT INCLUDING FITMENTS FOR CLASSIFICATIONS A & B1 SHALL BE AS FOLLOWS UNLESS OTHERWISE NOTED:

- FOR AREAS GREATER THAN 1km FROM COAST

ELEMENT	FORMED AND COVERED	FORMED AND EXPOSED
SLABS AND WALLS	20mm	30mm
BEAMS	25mm	40mm
COLUMNS	40mm	50mm
FOOTINGS	-	65mm

FOR AREAS OUTSIDE THE ABOVE REFER TO AS3600 FOR COVER REQUIREMENTS AND PRIOR TO STEEL SCHEDULING OR ORDERING CONTACT THIS OFFICE FOR CONFIRMATION OF COVERS

C4 CONCRETE COVERS SHALL BE MAINTAINED BY THE USE OF APPROVED CHAIRS AND SUPPORTS AT A MINIMUM OF 1200MM CRS. CONDUITS, PIPES ETC. ARE NOT TO BE PLACED IN THE CONCRETE COVER. CONTRACTOR TO ENSURE CORRECT COVER CAN BE OBTAINED DURING REVIEW OF DOCUMENTS PRIOR TO TENDER SUBMISSION

C5 REINFORCEMENT MUST BE SECURELY FIXED IN POSITION TO PREVENT DISPLACEMENT WITH APPROVED SUPPORT METHODS AND SPACING

C6 CONCRETE SIZES SHOWN DO NOT INCLUDE FINISHES AND MUST NOT BE REDUCED. NO PENETRATIONS, CHASES, OR EMBEDMENTS OTHER THAN SHOWN ON THE STRUCTURAL DRAWINGS SHALL BE MADE WITHOUT WRITTEN APPROVAL FROM THE DESIGN ENGINEER.

C7 CONCRETE MEMBERS HAVE TO REACH A MINIMUM STRENGTH PRIOR TO CONSTRUCTION LOADING, CONTRACTOR TO CONFIRM WITH DESIGN ENGINEER REQUIRED STRENGTH

C8 DIAGONAL BARS 3-N12 BARS OR 3-L11TM X 2000 MM LONG SHALL BE PLACED ACROSS EACH INTERNAL CORNER (& OPENING) OF SLABS AND WALLS IN TOP SURFACE.

C9 REINFORCEMENT IS REPRESENTED DIAGRAMMATIC ALLY AND IS NOT NECESSARILY A TRUE PROJECTION. SPLICES ARE TO BE MADE ONLY IN LOCATIONS AS NOMINATED ON DRAWINGS UNLESS GIVEN WRITTEN APPROVAL FROM THE DESIGN ENGINEER. WELDING OF REINFORCEMENT IS NOT PERMITTED UNLESS NOMINATED ON DRAWINGS.

C10 CONSTRUCTION JOINTS WHERE NOT SHOWN ON DRAWINGS SHALL BE LOCATED TO THE APPROVAL OF THE DESIGN ENGINEER

C11 ALL CONCRETE SHALL BE MOIST CURED FOR A MINIMUM OF 7 DAYS AFTER CONCRETE POUR, UNLESS OTHERWISE NOTED IN DOCUMENTS.

C12 SAW CUT JOINTS WHERE SHOWN ON THE DRAWINGS SHALL BE MADE WITHIN 24 HOURS OF COMPLETION OF CONCRETE POUR.

C13 FORM WORK SHALL BE LEFT IN PLACE FOR THE MINIMUM TIME AS NOTED BELOW UNLESS OTHERWISE APPROVED IN WRITING FROM THE DESIGN ENGINEER.

- BEAM SIDES, VERTICAL WALLS AND COLUMNS 4 DAYS
- SLABS UP TO 4.5M SPANS (RE-PROPPING REQUIRED), 8 DAYS
- REMOVAL OF PROPS UNDER SLAB 28 DAYS
- BEAM SOFFITS UP TO 7.6M (PROPPING REQUIRED) 14DAYS
- REMOVAL OF PROPS UNDER BEAMS 24 DAYS

C14 ALL MATERIALS AND CONSTRUCTION IS TO BE IN ACCORDANCE WITH AS3600 AND AS1509

FOOTING, SLAB & GROUND NOTES

F1 ALL FOOTINGS ARE TO BE BASED ON NATURAL MATERIALS WITH A MINIMUM SAFE BEARING CAPACITY 150KPa FOR STRIP & PAD FOOTINGS,100KPa FOR SLAB BEAMS (U.N.O). THE DESIGN ENGINEER IS TO BE CONTACTED PRIOR TO POURING OF ANY CONCRETE TO VERIFY CONDITIONS. ALL GROUND WORKS, FOUNDATIONS AND BATTERS ARE TO BE CARRIED OUT IN ACCORDANCE WITH THE RECOMMENDATIONS OUTLINED IN THE GEOTECHNICAL REPORTS

F2 ALL FOUNDATIONS SLABS ETC. ARE TO BE INSPECTED BY THE RELEVANT AUTHORITY PRIOR TO CONCRETE POURING

F3 ALL GROUND WORKS, FOUNDATIONS AND BATTERS ARE TO BE CARRIED OUT IN ACCORDANCE WITH THE RECOMMENDATIONS OUTLINED IN THE AUSTRALIAN STANDARD AS2870. CONTRACTOR TO CARRY OUT THE RELEVANT INVESTIGATIONS PRIOR OR COMMENCEMENT OF WORKS TO ENSURE NOMINATED SLABS IS APPLICABLE U.N.O

F4 CONTRACTOR TO ENSURE THAT AREAS ADJACENT TO STRUCTURE ARE WELL GRADED & DRAINED TO PREVENT COLLECTION OF SURFACE WATER.

F5 DESIGN ENGINEER TO ADVISE ON THE SLAB THICKNESS WHERE HOT COILS ARE TO BE EMBEDDED INTO SLAB. WHERE NOT SPECIFIED ON ENGINEERS DOCUMENTS

F6 ALL JUNCTIONS, PIPES & CONNECTIONS ETC. OF DRAINAGE, SEWERAGE & SERVICE MATERIALS FOR THE PROJECT ARE TO INCORPORATE RELATIVE MOVEMENT OF THE STRUCTURE, SURFACE AND SUB-SURFACE CONDITIONS.

F7 WHERE FILL UNDER SLABS EXCEEDS 100MM IN DEPTH THE FILLING SHALL CONSIST OF :

(a) GRANULAR MATERIAL TO A DEPTH NOT GREATER THAN 600MM AND COMPACTED IN NOT GREATER THAN 150MM LAYERS.

(b) CLAY MATERIAL TO A DEPTH NOT GREATER THAN 300MM AND COMPACTED IN NOT GREATER THAN 150MM LAYERS. PROPOSED FILL MATERIAL DETAILS ARE TO BE SUBMITTED TO THE DESIGN ENGINEER FOR APPROVAL

F8 ALL DRAINAGE, SEWER & SERVICES AFFECTED BY FOUNDATION MOVEMENTS ARE TO BE FITTED WITH THE APPROPRIATE FLEXIBLE CONNECTIONS

F9 REINFORCEMENT LAPS TO BE AS FOLLOWS UNLESS OTHERWISE NOTED:

(a) N12 BARS, 500MM MINIMUM
(b) N16 BARS, 700MM MINIMUM
(c) TRENCH MESH SPLICE NO LESS THAN 700MM
(d) TEE INTERSECTION & CORNERS TO BE FULL WIDTH
(e) SLAB REINFORCEMENT AS NOTED

F10 ALL EXCAVATIONS SHALL BE TAKEN OUT ACCURATELY TO THE LINES, LEVELS AND GRADES REQUIRED BY THE DOCUMENTS IN WHATEVER MATERIAL MAY BE ENCOUNTERED. (UNSUITABLE MATERIAL TO BE REMOVED & APPROVED BACKFILL REPLACED)

STRUCTURAL STEELWORKS

S1 ALL WORKMANSHIP AND MATERIALS SHALL BE IN ACCORDANCE WITH: AS1538, AS3828, & AS4100

S2 UNLESS NOTED OTHERWISE:

- ALL FILLET WELDS SHALL BE 6mm CONTINUOUS FILLET WELDS (U.N.O.)
- ALL WELDING TO BE CARRIED OUT WITH E41XX ELECTRODES
- ALL CLEATS AND GUSSET PLATES SHALL BE 8MM THICK GRADE 300 U.N.O

S3 THE GRADE OF STRUCTURAL STEEL SHALL BE GRADE 300 U.N.O FOR UNIVERSAL COLUMNS AND BEAMS

S4 ALL SURFACE PREPARATION SHALL BE IN ACCORDANCE WITH SPECIFICATIONS AND ARCHITECTURAL DOCUMENTATION

S5 ALL STEEL WORK OTHER THAN ENCASED BY CONCRETE AND MATING SURFACES OR FRICTION TYPE CONNECTIONS SHALL BE GIVEN ONE COAT OF STEEL PRIMING PAINT

S6 ALL BEAMS AND LINTELS ARE TO HAVE A MINIMUM OF 110mm POSITIVE BEARING ON MASONRY OR SUPPORTED ON 90×90×5.0 S.H.S UNLESS OTHERWISE NOTED

S7 ALL EXPOSED STEEL WORK PROTECTION FROM CORROSION IS TO COMPLY WITH BCA VOLUME 2 - PART 3.4.2.2 AND WHERE APPLICABLE AS1397

BRICKWORK & BLOCK WORK

B1 LOAD BEARING BRICKWORK SHALL HAVE A MINIMUM CHARACTERISTIC COMPRESSIVE STRENGTH OF 30MPa OR AS NOTED ON DRAWINGS. BLOCK WORK SHALL BE GRADE 15 MPa

B2 UNLESS NOTED OTHERWISE MORTAR SHALL BE MIXED IN THE FOLLOWING PROPORTIONS:

- BELOW DAMP COURSE "1 CEMENT, 1/4 LIME, 3 SAND "
- ABOVE DAMP COURSE "1 CEMENT, 1 LIME, 6 SAND "

B3 NON LOAD BEARING WALLS ARE TO BE KEPT 20MM MINIMUM CLEAR OF UNDERSIDE OF SLABS AND/OR BEAMS/FLOOR JOISTS

B4 CONTROL JOINTS UNLESS OTHERWISE DETAILED ON THE ARCHITECTURAL OR ENGINEERS DRAWINGS ARE TO BE PROVIDED AT 6M MAX. CENTERS (AS A GUIDE ONLY) MASONRY WALLS TO BE ARTICULATED BY FULL HEIGHT JOINTS TO ARCHITECTURAL DOCUMENTS.

B5 MASONRY ANCHORS AND ACCESSORIES ARE TO BE INSTALLED AS PER THE MANUFACTURERS RECOMMENDATIONS AND RELEVANT AUSTRALIAN STANDARDS AND INTO SOLID COURSE MASONRY

B6 CAVITY WALLS WITH A MAXIMUM OF 80mm CAVITY PROVIDE MASONRY FLEXIBLE ANCHORS "POSI-TIE" AT 340mm VERTICAL & 900mm HORIZONTAL CENTERS AS A MINIMUM.

B7 AT VERTICAL CONTROL JOINTS PROVIDE MASONRY FLEXIBLE ANCHORS MFA3-3A AT 340mm MAXIMUM CENTERS, REFER TO ARCHITECTURAL FOR FILLER MATERIALS

B8 A FULL HEIGHT OPENING OR ARTICULATION JOINT SHOULD BE ESTABLISHED WHERE THE EXTENSION JOINS THE EXISTING BUILDING. DOWEL BARS AS DETAILED SHOULD BE DRILLED END EPOXY GROUTED TO THE EXISTING FOOTING

TIMBER

T1 ALL TIMBER CONSTRUCTION AND ANY OTHER MEMBERS NOT SHOWN SHALL COMPLY WITH THE TIMBER FRAMING CODE AS1684 AND AS 1720, F17 TO BE UTILIZED UNLESS OTHERWISE NOTED. TIMBER TO CONFORM WITH CLASS B STRAIGHTNESS AS A MINIMUM

T2 ALL BEAMS AND LINTELS ARE TO HAVE A MINIMUM OF 110MM POSITIVE BEARING ON BRICKWORK/ BLOCKWORK

T3 PROVIDE 100MM X 100MM CONCRETE STUMP AND 450MM SQUARE X 450 DEEP MASS CONCRETE PAD FOOTINGS UNDER ALL TIMBER POSTS AS A MINIMUM REQUIREMENT (REFER TO GROUND NOTES FOR ADDITIONAL ITEMS U.N.O)

T4 PROVIDE A MINIMUM OF 2 NO FLOOR JOISTS UNDER ALL PARALLEL WALLS ABOVE UNLESS OTHERWISE NOTED ON DRAWINGS

T5 ALL LAMINATED TIMBER BEAMS TO BE SUPPLIED WITH MANUFACTURERS PRE CAMBER OR UNLESS OTHERWISE NOTED

T6 ALL EXPOSED TIMBER SHALL BE WATERPROOFED & TREATED AS PER MANUFACTURER'S SPECIFICATIONS.

T7 ALL TIMBER TO BE USED IN THIS PROJECT SHALL BE DRY AT THE TIME OF CONSTRUCTION.

T8 ALL TIE DOWNS, CONNECTIONS, BRACING SHALL COMPLY WITH AS1684 - 2010

T9 ALL TIMBER BEAMS WITH MULTIPLE MEMBERS ARE TO BE LAMINATED IN ACCORDANCE WITH AS1684

FOOTING: ANGLE OF REPOSE


F1 PROPOSED FOOTING/SLAB BEAMS AND PROPOSED EXCAVATIONS MUST NOT UNDERMINE EXISTING FOOTINGS.

F2 ENSURE ADEQUATE ANGLE OF REPOSE IS ACHIEVED AT ALL TIMES (REFER TO DETAILS BELOW)

F3 NOTIFY THIS OFFICE IF FOOTING UNDERMINING OCCURS

F4 EXISTING AMENITY SERVICE PIPES ARE TO BE CONFIRMED PRIOR TO ANY CONSTRUCTION WORKS COMMENCING


F5 NO PROPOSED SERVICE LINES/CONDUITS ARE TO UNDERMINE ANY FOOTINGS



Duplicate

REVISION	COMMENT	DATE
C1	CONSTRUCTION ISSUE	
-	-	-
-	-	-
-	-	-

Design:
Drawn:
Scale: 1:100 @ A3
Job no:
Revision: C1
Sheet: S01 / 16
Title: GENERAL NOTES



LEGEND

WHERE NOMINATED 3-L11TM OR 3-N12 BARS (x2000 LONG) TIED TO UNDERSIDE OF SLAB MESH

WHERE HATCHED DENOTES STEP DOWN OF WAFFLE BOXES

DENOTES STARTING POINT FOR LAYOUT OF WAFFLE POD BOXES

DENOTES SLAB EDGE BEAM EXTENSION TO FIRST INTERNAL RIB MINIMUM

DENOTES STRIP FOOTING TO CONTINUE TO FIRST INTERNAL RIB MINIMUM

DENOTES LOCATION OF ADDITIONAL 1-N16 BAR TIED TO TOP MESH

SF1 — 300WIDE × 600 DEEP STRIP FOOTING FOUNDED MINIMUM 100mm INTO STIFF NATURAL SILTY CLAY WITH 100kPa BEARING CAPACITY. REINFORCEMENT: 3-L16TM TOP & BOTTOM TYPICAL

DENOTES A 400 WIDE SLAB EDGE BEAM WITH 4-L16TM BOTTOM AND 3-L16TM TOP. REFER TO NOMINATED SECTION

GROUND FLOOR SLAB PLAN

NOTE -
ANY NEW FILL PLACED ON SITE AS A RESULT OF CUT AND FILL OPERATION IS NOT TO EXCEED 300mm. ANY NEW FILLING TO BE COMPACTED IN ACCORDANCE WITH AS2870-2011. REFER TO CLAUSE 6.4.2.(A)

100 THICK CONCRETE WAFFLE SLAB, SL82 FABRIC TOP WITH 30mm COVER, 300 DEEP PODS, ON 0.2mm POLYTHENE MEMBRANE (LAPPED 200 AND TAPED AT JOINTS) OVER 25-50mm LEVELING QUARRY PRODUCT.

-SLAB EDGE BEAMS TO BE 400 DEEP x 300 WIDE TYPICAL WITH 3-L16TM TOP & 3-L16TM BOTTOM U.N.O.

-SLAB INTERNAL BEAMS TO BE 400 DEEP x 110 WIDE TYPICAL WITH 1-N16 TOP AS PER SLAB PLAN & 1-N16 BOTTOM U.N.O.

CONCRETE STRENGTH = 20MPa AFTER 28 DAYS

NOTE -
FALL — GROUND SURFACE TO SLOPE AWAY FROM DWELLING 1 IN 20 FALL FOR 1.0m. WATER TO BE COLLECTED BY STORM WATER SYSTEM, SPOON DRAIN.


SLAB DESIGN BASED ON FULL ARTICULATED MASONRY VENEER AS PER AS2870 - 2011

GEOTECHNICAL REPORT UNDERTAKEN BY:
REF NO. : 09789-19 (DATED 23/07/2019)
COMPANY: HOME & INDUSTRIAL SOILTEST P/L
SITE CLASS: 'P' (AS 2870 - 2011)
THESE PLANS SHOULD BE READ IN CONJUNCTION WITH GEOTECHNICAL REPORT


REVISION	COMMENT	DATE
-	-	-
-	-	-
-	-	-
C1	CONSTRUCTION ISSUE	

Design:
Drawn:
Scale: 1:100 @ A3
Job no:
Revision: C1
Sheet: S02 / 16
Title: GROUND FLOOR SLAB PLAN

Education



TYPICAL SLAB EXTERNAL EDGE BEAM
CROSS SECTION



TYPICAL SLAB INTERNAL RIB
CROSS SECTION

WAFFLE SLAB SCHEDULE	
SLAB DETAILS	
OVERALL SLAB DEPTH	400mm
POD DEPTH	300mm
SLAB THICKNESS	100mm
EXTERNAL BEAM WIDTH	300mm
INTERNAL RIB WIDTH	110mm
TOP REINFORCEMENT	
SLAB FABRIC	SL82 FABRIC TOP
EXTERNAL BEAM	3-L16TM
INTERNAL RIB	AS PER SLAB PLAN
BOTTOM REINFORCEMENT	
EXTERNAL BEAM	3-L16TM
INTERNAL RIB	1-N16 BAR
ALL SLAB COMPONENTS AS PER THIS TABLE U.N.O	

CONCRETE STRENGTH = 20mPa AFTER 28 DAYS

NOTES -

1. SLAB DIMENSIONS AND DETAILS (FLOOR STEP DOWNS, RECESSES, ETC) MUST BE VERIFIED FROM ARCHITECTURAL DRAWINGS PRIOR TO CONSTRUCTION. ALL DIMENSIONS ARE IN MILLIMETERS (U.N.O).
2. WAFFLE DETAILS SHALL COMPLY WITH AS2870 - 2011
3. WAFFLE RAFT SHALL BE PREPARED IN ACCORDANCE WITH THIS WAFFLE RAFT LAYOUT AND PODS INSTALLED AS PER MANUFACTURERS RECOMMENDATIONS. CARE MUST BE TAKEN DURING CONSTRUCTION TO PREVENT PUNCTURE OF THE PLASTIC MEMBRANE.
4. CONCRETE SHALL BE 20 MPa GRADE AND 100mm SLUMP MIN. CONCRETE SHALL BE CURED FOR AT LEAST 7 DAYS PRIOR TO PLACING BRICKWORK.
5. ALL RE-ENTRANT CORNERS SHALL BE 3-L11TM OR 3-N12 BARS 2000mm LONG PLACED AS SHOWN ON THE DRAWING. THESE MAY BE TIED TO THE UNDERSIDE OF THE SLAB MESH
6. REFER TO GENERAL NOTES SHEET FOR ALL REINFORCEMENT LAPPING AND COVER REQUIREMENTS

CONSTRUCTION TECHNIQUES -

THE FOLLOWING CONSTRUCTION TECHNIQUES SHALL IN GENERAL BE FOLLOWED IN CONSTRUCTION THE WAFFLE RAFT.

1. SCRAPE VEGETATION AND ROOTS OFF THE BUILDING AREA. MINIMUM SCRAPE DEPTH OF 100MM SHOULD BE CARRIED OUT.
2. CUT SITE TO FORM A LEVEL BENCH. ANY NEW FILL PLACED AS A RESULT OF CUT AND FILL OPERATION IS NOT TO EXCEED 300 MM. ANY NEW FILLING TO BE COMPACTED IN ACCORDANCE WITH AS2870-2011 REFER TO CLAUSE 6.4.2 (A)
3. PLACE THE LAYER OF QUARRY PRODUCT OVER THE BUILDING AREA WHICH SHALL EXTEND AT LEAST 1.0 M OUTSIDE THE BUILDING LINE.
4. SET UP STRING LINES, EDGE BOARDS, AND FORMWORK.
5. PLUMBER SHALL LAY WASTE PIPES BELOW GROUND SURFACE AT MINIMUM GRADE. RISERS ARE TO BE STAKED FIRMLY
6. PREPARE WAFFLE RAFT WITHIN FORMWORK IN ACCORDANCE WITH THE FOOTING PLAN AND DETAILS. USE MINIMUM OF 0.2MM APPROVED PLASTIC MEMBRANE UNDER WAFFLE PODS AND RIBS, AND TO CONTINUE AROUND EDGE REBATE. WAFFLE PODS SHALL BE CUT AND TAPED AROUND PLUMBING PIPES

IMPORTANT NOTE -

1. THIS SLAB HAS BEEN DESIGNED BASED ON A GOOD SITE DRAINAGE AS SHOWN IN TYPICAL DRAINAGE DETAILS
2. DESIGN FOR EXISTING TREES (IF REQUIRED) ARE SHOWN IN THIS DRAWING DOCUMENT ON THE BASIS OF INFORMATION SUPPLIED TO THIS OFFICE AT THE TIME OF DOCUMENTATION. THIS OFFICE SHOULD BE ADVISED IMMEDIATELY IF THERE IS DISCREPANCIES ON THE TREE INFORMATION.
3. UNLESS OTHERWISE DESIGNED FOR, TREES AND/OR LARGE SHRUBS SHOULD NOT BE ALLOWED TO GROW NEAR THE BUILDING WITHIN A DISTANCE EQUIVALENT TO THE MATURE HEIGHT OF THE TREE. THE DISTANCE SHOULD BE INCREASED BY 50% WHERE THERE ARE GROUPS OR ROWS OF TREES.
4. THE HOMEOWNER SHOULD BE AWARE OF THEIR RESPONSIBILITY TO MAINTAIN THE FOOTING SYSTEM AFTER OCCUPYING THE BUILDING. THIS IS CONTAINED IN THE CSIRO PUBLICATION "BTF-18-FOUNDATION MAINTENANCE AND FOOTING PERFORMANCE: A HOME OWNERS GUIDE". THIS COULD BE PURCHASED FROM: FREECALL 1300 788 000 OR ONLINE AT: http://publish.csiro.au/pid/7076.htm

Edition only

REVISION	COMMENT	DATE
-	-	-
-	-	-
-	-	-
C1	CONSTRUCTION ISSUE	

Project:

Design:

Drawn:


Scale: 1:20 @ A3

Revision: C1


Job no:

Sheet: S03 / 16


Title: SLAB DETAILS




TYPICAL SLAB STEP DOWN DETAIL




SECTION G.01 --



SECTION G.02 --



SECTION G.03 --




SECTION G.04 --


Education use only

REVISION	COMMENT	DATE
C1	CONSTRUCTION ISSUE	
-	-	-
-	-	-
-	-	-

Design:
Drawn:
Scale: 1:20 @ A3
Job no:
Revision: C1
Sheet: S04 / 16
Title: SLAB DETAILS




SECTION G.05 --




TYPICAL DEEP EDGE REBATE UPTO 650 IN HEIGHT


STRIP FOOTING SCHEDULE	
STRIP FOOTING (SF1) DETAILS	
STRIP FOOTING DEPTH	600mm MIN.
STRIP FOOTING WIDTH	300mm
REINFORCEMENT (TOP & BOTTOM)	3-L16TM
STRIP FOOTING (SF1) TO BE FOUNDED A MINIMUM 100mm INTO STIFF NATURAL SILTY CLAY WITH A MINIMUM 100kPa BEARING CAPACITY	



TYPICAL WALL OVERHANG TO SLAB
RECTIFICATION DETAIL UPTO:
10mm - 20mm FOR BRICKWORK
& 35mm FOR FRAME OVERHANG



TYPICAL STRIP FOOTING DETAIL - (SF1)




STRIP FOOTING TO WAFFLE CONNECTION DETAIL

Education use only

REVISION	COMMENT	DATE
-	-	-
-	-	-
-	-	-
C1	CONSTRUCTION ISSUE	

Design:
Drawn:
Scale: 1:20 @ A3
Job no:
Revision: C1
Sheet: S05 / 16
Title: SLAB DETAILS



ROOF FRAMING PLAN

Education use only

LEGEND

DENOTES WALL UNDER

DENOTES INTERNAL LOAD BEARING WALL UNDER

NOTE -
ALL TIE DOWNS AND BRACING AS PER AS1684 - 2010

LINTEL SCHEDULE - ROOF ONLY (RL) (U.N.O)

LINTEL	SIZE	COLUMN
0 - 600	90x45 MGP10	DS1
601 - 1600	140x42 LVL15	DS1
1601 - 2000	190x42 LVL15	DS1
2001 - 2800	240x42 LVL15	TS1
2801 - 3000	2-240x42 LVL15	TS1

GIRDER TRUSS STUD SUPPORT SCHEDULE


MAX TRUSS WIDTH	SUPPORT AT EXTERNAL WALL	SUPPORT AT INTERNAL LBW
12m	3-90x35 MGP10	NIL
14m (WITH INTERNAL LBW)	2-90x35 MGP10	3-90x45 MGP10
NOTE - THIS TABLE IS NOT APPLICABLE TO GIRDER TRUSSES SUPPORTING OTHER GIRDER TRUSSES		
NOTE - TABLE COLUMN SIZES FOR MAX. STUD HEIGHT 2580 (U.N.O)		

MEMBER SCHEDULE

MARK	MEMBER
RL	ROOF LINTELS. REFER TO LINTEL SCHEDULE
L1	366x60 GL13
L2	190x42 LVL15
L3	140x42 LVL15
DS1	2-90x35 MGP10
TS1	3-90x35 MGP10
DS	2-90x45 MGP10
C4	50x50x3.0 SHS
GT	GIRDER TRUSS - ASSUMED LOCATION TO BE CONFIRMED BY TRUSS MANUFACTURER
P1	2-90x35 MGP10 TEMPORARY ONLY TO BE REMOVED IF L2 IS SUPPORTED BY BRICKWORK

REVISION	COMMENT	DATE
-	-	-
-	-	-
-	-	-
C1	CONSTRUCTION ISSUE	

Design:
Drawn:
Scale: 1:100 @ A3
Revision: C1
Job no:
Sheet: S06 / 16
Title: ROOF FRAMING PLAN



GROUND FLOOR WALL BRACING PLAN

BRACING DESIGN BASED ON 'N1'
WIND RATING

LENGTH OF BRACE — (B900)
TYPE OF BRACE

(B) DENOTES THE LOCATION OF TYPE B, 4.8mm HARDBOARD BRACING TO BE INSTALLED AS PER AS1684 - 2010 TABLE 8.18 (M). REFER TO BRACING DETAILS FOR EXTRACT

(C) DENOTES THE LOCATION OF DIAGONAL BRACING ANGLE STRAP BRACE TO BE INSTALLED AS PER AS1684 - 2010 TABLE 8.18 (C). REFER TO BRACING DETAILS FOR EXTRACT. C2700 = 2400 - 2700 IN LENGTH.

(D) DENOTES THE LOCATION OF BRACING DIAGONAL CROSS METAL STRAP BRACE OR SPEED BRACE TO BE INSTALLED AS PER AS1684 - 2010 TABLE 8.18 (D). REFER TO BRACING DETAILS FOR EXTRACT

NOTE -
ALL FLOOR JOISTS, ROOF TRUSSES, RAFTERS ON BRACING WALLS, TO BE CONNECTED TO BRACING WALLS IN AS SHOWN IN SECTIONS 'BR1'

REFER TO DETAIL 'BR1' FOR SOLID FLOOR JOISTS, ROOF TRUSSES, RAFTERS TO BRACING WALL CONNECTION DETAILS (PERPENDICULAR)

NOTE -
FOR TYPE (C) & (D) BRACING ALTERNATIVE TO 30×.08mm GALV. STRAP LOOP; ADOPT PRYDA SST BRACKET

Education use only

REVISION	COMMENT	DATE
C1	CONSTRUCTION ISSUE	
-	-	-
-	-	
-	-	-

Project:


Design:
Drawn:
Scale: 1:100 @ A3

Revision: C1

Job no:

Sheet: S07 / 16

Title: GROUND FLOOR WALL BRACING PLAN



ARTICULATION JOINT PLAN

Education use only

LEGEND


AJ DENOTES ADDITIONAL ARTICULATION JOINT IN BRICKWORK

REVISION	COMMENT	DATE
C1	CONSTRUCTION ISSUE	
-	-	-
-	-	-
-	-	-


Design:
Drawn:
Scale: 1:100 @ A3
Revision: C1
Job no:
Sheet: S08 / 16
Title: ARTICULATION JOINT PLAN

TIMBER STUD SCHEDULE


ALL STUDS SHALL BE NAIL LAMINATED IN ACCORDANCE WITH AS1684.2		DS	DS1	TS	TS1	DC	TC	QC
		90×45	90×35	90×45	90×35	90×45	90×45	90×45
		MGP10	MGP10	MGP10	MGP10	F17 KDHW	F17 KDHW	F17 KDHW
LINTEL	NO. OF BEARING STUD	1	1	1	1	1	1	2
	NO. OF JAMB STUD	1	1	2	2	1	2	2
BEAM	NO. OF BEARING STUD	2	2	3	3	2	3	4




LINTEL SUPPORT ON STUDS




BEAM SUPPORT ON STUDS



STEEL COLUMN TO PORCH BEAM DETAIL TYPICAL



ALFRESCO/PORCH TEMPORARY PROP PRIOR TO INSTALLING STEEL MULLION



TYPICAL ARTICULATION JOINT BRICKWORK DETAIL

ARTICULATION JOINT THICKNESS - SPACING TABLE

SOIL CLASS	MASONRY WALL CONSTRUCTION & SURFACE FINISH	UP TO 4m HIGH FOR (AT) = 10mm	4m TO 8.5 HIGH FOR (AT) = 15mm
M, M-D	EXTERNAL FACE MASONRY	6.0	6.0
	EXTERNAL RENDERED &/OR PAINTED MASONRY	5.5	5.5
H1, H1-D	EXTERNAL FACE MASONRY	5.5	5.5
	EXTERNAL RENDERED &/OR PAINTED MASONRY	5.0	5.0
H2, H2-D	EXTERNAL FACE MASONRY	5.0	5.0
	EXTERNAL RENDERED &/OR PAINTED MASONRY	4.5	4.5
SIZES BASED AS4773.1 - 2015 MASONRY IN SMALL BUILDINGS. REFER TO TABLE 13.1			

Education use only

REVISION	COMMENT	DATE
-	-	-
-	-	-
-	-	-
C1	CONSTRUCTION ISSUE	


Title: FRAMING DETAILS

Design:
Drawn:
Scale: 1:10 @ A3
Job no:
Revision: C1
Sheet: S09 / 16

SINGLE STOREY TIMBER FRAMING SCHEDULE - (TILED ROOF)

LOCATION	MINIMUM SIZE	NOTES		
BOTTOM PLATE	35×90 MGP10	SUPPORTED ON CONTINUOUS SLAB FLOOR		
TOP PLATE	2-35×90 MGP12	MAX. RLW = 7.5m (LOAD BEARING)		
WALL STUDS	MINIMUM SIZE	MAX. HEIGHT	MAXIMUM RLW	
			INTERNAL LBW	EXTERNAL LBW
	90×35 MGP10	2700	@600 CRS. - MAX. RLW=7.5m	@600 CRS. - MAX. RLW=7.5m
	MAXIMUM NOTCHING TO STUDS FOR BRACING TO BE 20mm			
NOGGINGS	STUD NOGGINGS @ NO MORE THAN 1350 CRS.			

RLW - ROOF LOAD WIDTH




Education use only

REVISION	COMMENT	DATE
-	-	-
-	-	-
-	-	-
C1	CONSTRUCTION ISSUE	


Design:
Drawn:
Scale: 1:10 @ A3
Job no:
Revision: C1
Sheet: S10 / 16
Title: FRAMING DETAILS

MINIMUM HARDBOARD THICKNESS 4.8mm	
FASTENER SPACING (mm)	
TOP & BOTTOM PLATES	40
VERTICAL EDGES & NOGGING	150
INTERMEDIATE STUDS	300




FIXING BOTTOM PLATE TO TIMBER FLOOR:
PLATES UP TO 38mm THICK
2-75x3.05mmØ NAILS TO EACH JOIST AT 450 MAX. CRS.
OR
PLATES 38mm TO 50mm THICK WITH 2-90x3.05mmØ NAILS TO EACH JOIST AT 450 MAX. CRS.

TYPE B - WALL BRACING



REFER 'TABLE 2' FOR SPACING OF SHEAR BLOCKS TO BRACED WALL

PERPENDICULAR BRACED WALL TO TRUSSES



NOTES:
1. TYPE B - HARDBOARD SHALL COMPLY WITH AS/NZS 1859.4.
2. HARDBOARD SHALL BE NAILED TO FRAME USING MINIMUM 30x2.8mmØ GALZANISED FLAT-HEAD NAILS OR EQUIVALENT.
3. NAILS SHALL BE LOCATED A MINIMUM OF 10mm FOR THE VERTICAL EDGES AND 15mm FROM THE TOP AND BOTTOM EDGES. MAXIMUM STUD SPACING = 600mm.
4. AT LEAST ONE SIDE OF THE BRACING WALL SHALL BE LINED WITH GYPSUM PLASTER BOARD OR EQUIVALENT.
5. PROVIDE A 2mm EXPANSION GAP AROUND THE PERIMETER OF EVERY HARDBOARD PANEL.
6. HORIZONTAL BUTT JOINTS ARE PERMITTED, PROVIDED FIXING TO NOGGING AT 40mm CENTRES.
7. BRACING PANEL MINIMUM WIDTH = 900mm.

TABLE 2 SPACING OF SHEAR BLOCK PAIRS PERPENDICULAR / PARALLEL TO BRACED WALLS	
BRACING TYPE	SPACING (mm)
A	1200
B	700
C	2700
D	1350
NOTE: MIN. 1 No PAIR OF SHEAR BLOCKS REQUIRED FOR EACH BRACED WALL	

BRACING WALL - BOTTOM PLATE END FIXING TO SLAB TYPICAL DETAIL

DETAIL X2 / ---

TYPE B - AS1684.2 - 2010 TABLE 8.18 (M) EXTRACT

CONCRETE FLOOR BRACING CAPACITY = 6.0kN/m
TIMBER FLOOR BRACING CAPACITY = 3.4kN/m

Construction use only

REVISION	COMMENT	DATE
-	-	-
-	-	-
-	-	-
C1	CONSTRUCTION ISSUE	


Design:
Drawn:
Scale: 1:10 @ A3
Job no:
Revision: C1
Sheet: S11 / 16
Title: BRACING DETAILS

NOTE 1.


OPTION 1. 1 No. PRYDA EZI STUD TIE SST

OPTION 2. 30x0.8mm GALV. METAL STRAP LOOPED OVER PLATE AND FIXED TO STUD WITH 3-30x2.8mmØ GALV. FLAT HEAD NAILS (OR EQUIVALENT) TO EACH END. ALTERNATIVELY, SINGLE STRAP TO BOTH SIDES WITH 3 NAILS PER STRAP END 'OR' EQUIVALENT ANCHORS OR OTHER FASTENERS.

OPTION 3. PRYDA STUD TIE ST3 'OR' ST4 'OR' STS3 'OR' PRYDA STRAP NAIL SN2C 'OR' SN2B ON BOTH SIDES OF THE FRAME.



TYPE C - WALL BRACING



BRACING WALL - BOTTOM PLATE END FIXING TO SLAB TYPICAL DETAIL

DETAIL X3 ---

NOTES:
TYPE C - TIMBER AND METAL ANGLE BRACES -
THE MAXIMUM DEPTH OF NOTCH OR SAW-CUT SHALL NOT EXCEED 20mm.
SAW-CUTS STUDS SHALL BE DESIGNED AS NOTCHED.

TYPE C - AS1684.2 - 2010 TABLE 8.18 (C) EXTRACT

BRACING CAPACITY = 1.5kN/m

Education use only

REVISION	COMMENT	DATE
C1	CONSTRUCTION ISSUE	
-	-	-
-	-	-
-	-	-


Design:
Drawn:
Scale: 1:10 @ A3
Job no:
Revision: C1
Sheet: S12 / 16
Title: BRACING DETAILS

NOTE 1A.

OPTION 1. 1 No. PRYDA EZI STUD TIE SST.


OPTION 2. 30×0.8MM GALV. METAL STRAP LOOPED OVER PLATE AND FIXED TO STUD WITH 4-30×2.8MMØ GALV. FLAT-HEAD NAILS (OR EQUIVALENT) TO EACH END.
ALTERNATIVELY PROVIDE SINGLE STRAPS TO BOTH SIDES, WITH 4 NAILS PER STRAP END OR EQUIVALENT ANCHORS OR OTHER FASTENERS.

OPTION 3. PRYDA STUD TIE ST3 'OR' STS3 'OR'
PRYDA STRAP NAIL SN2 ON EACH WALL FACE.



TYPE D - WALL BRACING

(D) - METAL STRAPS - TENSIONED - WITH STUD STRAPS



BRACING WALL - BOTTOM PLATE END FIXING TO SLAB TYPICAL DETAIL

DETAIL X5 ---


TYPE D - AS1684.2 - 2010 TABLE 8.18 (D) EXTRACT

BRACING CAPACITY = 3.0kN/m

Education Use only

REVISION	COMMENT	DATE
C1	CONSTRUCTION ISSUE	
-	-	-
-	-	-
-	-	-

Design:
Drawn:
Scale: 1:10 @ A3
Job no:
Title: BRACING DETAILS
Revision: C1
Sheet: S13 / 16



Education use only

SURFACE DRAINAGE PLAN

LEGEND


DENOTES 100ø UPVC STORMWATER PIPE TO GRADE TO LPOD, TO BE INSTALLED IN ACCORDANCE WITH AS3500

DP — DENOTES DOWN PIPE, REFER TO ARCHITECT'S DOCUMENTATION FOR SIZING


D □ — DENOTES DRAIN, REFER TO ARCHITECT'S DOCUMENTATION FOR SIZING

REVISION	COMMENT	DATE
C1	CONSTRUCTION ISSUE	
-	-	-
-	-	-
-	-	-

Design:
Drawn:
Scale: 1:100 @ A3
Job no:
Revision: C1
Sheet: S14 / 16
Title: SURFACE DRAINAGE PLAN



TYPICAL CUT AND FILL SITE DRAINAGE DETAIL



TYPICAL SEWER EDGE BEAM DETAIL

DRAINAGE REQUIREMENTS

AS PER AS 2870-2011 SECTION 5.6.3

1. SURFACE DRAINAGE OF SITE TO BE CONTROLLED FROM START OF SITE PREPARATION AND SHOULD BE COMPLETED BY END OF CONSTRUCTION
2. TRENCH BASES TO SLOPE AWAY FROM BUILDING
3. TOP 300MM OF TRENCHES TO BE BACK-FILLED WITH MOIST COMPACTED CLAY WITHIN 1.5M FROM THE BUILDING
4. TRENCHES UNDER FOOTINGS TO BE PLUGGED WITH CLAY
5. SUBSOIL DRAINS NOT TO BE WITHIN 1.5M FROM BUILDING UNLESS DESIGNED IN ACCORDANCE WITH ENGINEERING PRINCIPLES

PLUMBING REQUIREMENTS


AS PER AS 2870 – 2011 SECTION 5.6.4

1. PENETRATION OF SERVICE PIPES AT EDGE BEAMS OR FOOTINGS TO BE AVOIDED WHERE PRACTICABLE. WHERE NECESSARY OR UNAVOIDABLE, SERVICE PIPE SHALL BE DETAILED TO ALLOW FOR MOVEMENT.
2. DRAINS EMERGING FROM UNDERNEATH THE BUILDING TO INCORPORATE FLEXIBLE JOINTS AND SHOULD ALLOW DIFFERENTIAL MOVEMENT IN ANY DIRECTION EQUAL TO THE ESTIMATED CHARACTERISTIC SURFACE MOVEMENT, YS.
3. ON SITE WASTE WATER TREATMENT UNITS TO BE LOCATED TO MINIMISE SOIL MOISTURE INCREASE WITHIN THE FOUNDATION.
4. DRAINAGE UNDER THE SLAB TO BE AVOIDED WHERE PRACTICABLE.
5. COLD AND HOT WATER PIPES NOT TO BE INSTALLED UNDER THE SLAB, UNLESS PIPES ARE INSTALLED WITHIN A CONDUIT SO THAT IF THE PIPE LEAKS IT WILL BE NOTICED ABOVE OR OUTSIDE THE SLAB


Education use only

REVISION	COMMENT	DATE
-	-	-
-	-	-
-	-	-
C1	CONSTRUCTION ISSUE	


Design:
Drawn:
Scale: 1:20 @ A3
Job no:
Revision: C1
Sheet: S15 / 16
Title: SITE DRAINAGE DETAILS



TYPICAL PAVED SITE DRAINAGE



TYPICAL FINAL SITE DRAINAGE



TYPICAL SERVICE PIPE WITHIN 1.5m OF EXTERNAL FOOTING

Education use only

REVISION	COMMENT	DATE
C1	CONSTRUCTION ISSUE	
-	-	-
-	-	-
-	-	-

Design:
Drawn:
Scale: 1:20 @ A3
Revision: C1
Job no:
Sheet: S16 / 16
Title: SITE DRAINAGE DETAILS